


2017-41



Author: Kilee Haase

Date: October 24, 2017

FIVE  NINES

Professional Services

Stage ESXi Hosts

- Update BIOS, Configure BIOS and Update Firmware
- Configure RAID, Configure DRAC and Install ESXi
- Set root password, Install license keys and Create local accounts
- Set IP address, Configure time and Performance tune
- Configure DNS and default route and Configure vSwitches
- Configure iSCSI round robin best practices
- Install Open Manage and Install PowerChute Agent

Stage SAN

- Update firmware, Configure group settings and Configure time
- Configure group name, Configure group IP and Configure admin accounts
- Configure notifications, Configure CHAP and Configure volume settings
- Configure management network and Configure Volumes
- Configure snapshot schedule and Configure iSCSI best practices

Onsite Installation

- Box equipment and ready it for transport and Unbox equipment
- Install rails and rack equipment and Cable equipment to network switches
- Perform cable management and Power on equipment
- Verify all equipment comes online properly

Install & Configure vCenter Appliance

- Create virtual machine, Name server and Install License key
- Specify SMTP server and Configure from email address
- Set Database retention settings and Configure vCenter alarms
- Configure snapshot report script and Install VMware Update Manager
- Create datacenter, Configure High Availability and Configure vMotion
- Test and verify High Availability and vMotion

Configure SAN Management Tools

- Install & configure Group Manager & SAN, or InfoSight
- Configure snapshot alerting and Configure iSCSI round robin

Perform P2V Operations

- Install VMware converter, Disable backups and Transfer FSMO roles (domain controller)
- Demote server (domain controller) and Shutdown database services
- Create conversion task, Monitor progress of task and Power on virtual machine
- Configure networking and Run remove hardware script
- Install VMware tools, Restart server and Promote server (domain controller)
- Transfer FSMO roles back (domain controller) and Verify volumes are in tact
- Start database services and Enable backups

Configure 1 NAS appliance

- Add hard drives to appliance, Update software and Configure IP address
- Configure users and Configure shared folder

Configure Spam Filter Account

- Create new company account and Configure default filter policies
- Configure disaster recovery settings and Create user accounts
- Configure outbound destination to Exchange server public IP address

Switch Staging and Configuration (4)

- Upgrade software image to the latest recommended version for each switch
- Apply best-practices base configuration and Configure VLANs and VLAN interfaces
- Configure trunks and port-channels and Configure access ports
- Create and configure switch stack and Configure best-practices for SAN stack
- Configure Layer 3 switch features

Professional Services

Switch Installation

- Mount and install new switch(es) and Migrate cabling and uplinks
- Test and verify LAN connectivity and Remove old switch(es)
- Complete rack re-cable/cleanup

Firewall Staging and Configuration

- Upgrade software image to the latest recommended version for each firewall
- Apply best-practices base configuration and Configure interfaces and IP addresses
- Configure static routes and Configure NAT and ACL for port forwards
- Configure IPsec L2L VPN(s) and Configure dynamic routing
- Non-Cisco Firewall Migration, Configure DHCP and Configure additional VPN

Firewall Installation

- Mount and install new firewall(s) and Test and verify LAN and Internet connectivity
- Test and verify external NAT and Remove old firewall(s)
- Test and verify WAN/VPN connectivity

Wireless Staging and Configuration

- Configure organization and install licensing in dashboard
- Configure network and up to two SSIDs and Customize and map each access point

Wireless Installation, Testing and Verification

- Mount wireless access points (10) and Test and verify connectivity

PROJECT NOTES & ASSUMPTIONS

- Down time will be required for hardware installation
- Down time will be required for virtualization of physical servers
- Project assumes 3 onsite trips
- Daily management and maintenance is included with Five Nines' Backups, but all restore requests are handled at current T&M rate
- Project assumes that there is sufficient bandwidth to support offsite backup replication
- Project assumes network cabling for each wireless access point will be run and terminated by a 3rd party cable installation company
- Project assumes adequate power and cooling will be available for new equipment. Additional power strips may be needed to accommodate PoE injectors
- Project assumes existing patch cables are in good enough condition and length to be reused for new equipment. Inadequate cabling will be replaced
- Additional wireless access points may be required if wireless coverage is determined to be inadequate

Subtotal **\$20,868.75**

Uptime Project



Kilee Haase

Prepared by:
Five Nines Technology Group, Inc.
 Kilee Haase
 402.486.7453
 kilee.haase@gonines.com

Prepared for:
Keith County Nebraska
 511 N. Spruce
 Ogallala, NE 69153
 Caleb Johnson
 calebjohnson@atcjet.net

Quote Information:
Quote #: 030640
 Version: 1
 Delivery Date: 10-24-2017
 Expiration Date: 11-30-2017

Summary

Professional Services	\$20,868.75
Total	\$20,868.75

[Handwritten Signature]
 Signature, Client
Chairman

Caleb W. Johnson
 Print, Client

Nov 1, 2017
 Date